

FIELD INVESTIGATIONS OF UNCONTROLLED HAZARDOUS WASTE SITES

FIT PROJECT

**TASK REPORT TO THE
ENVIRONMENTAL PROTECTION AGENCY
CONTRACT NO. 68-01-6056**

DRAFT

SUBJECT TO REVISION

**PRELIMINARY SITE ASSESSMENT
HOLDEN LANDFILL SITE
Wachusett River Street
Holden, Massachusetts**

**DRAFT
SUBJECT TO REVISION**

December 8, 1981

TDD No. F1-8109-04

**Prepared by: Ecology and Environment, Inc.
Field Investigation Team (FIT)
Region 1**

Submitted to: John Hackler

ecology and environment, inc.

International Specialists in the Environmental Sciences

PRELIMINARY SITE ASSESSMENT
for
Holden Landfill Site
Wachusett River Street
Holden, Massachusetts

TDD #: F1-8109-04

Site Name: Holden Landfill Site

Address: Wachusett River Street
Holden, Massachusetts

Telephone: (617) 829-6561

Owner: Town of Holden

Principal Contact at Site: Mr. Alan Berg, Holden Town Engineer

Contributors

**Ecology and Environment, Inc.
Region 1 Field Investigation team**

TDD # F1-8109-04

PRELIMINARY SITE ASSESSMENT

**Holden Landfill Site
Wachusett River Street
Holden, Massachusetts**

The following Region 1 Field Investigation Team members made major contributions to this study in the capacities noted:

Project Manager	-	Christopher Hagger
Site Hydrogeology	-	William Norman

TABLE OF CONTENTS

	<u>Page</u>
FIGURES:	iv
TABLES:	v
SECTION 1: INTRODUCTION	1-1
PURPOSE OF ASSESSMENT	1-1
OBJECTIVE	1-1
SECTION 2: SITE BACKGROUND	2-1
SITE DESCRIPTION	2-1
SITE ACTIVITY	2-3
SITE HISTORY	2-3
SITE GEOLOGY/HYDROGEOLOGY	2-7
SECTION 3: HAZARDS ALLEDGED AND/OR IDENTIFIED	3-1
WASTER CHARACTERISTICS	3-1
Types and Quantities	3-1
Waste Management/Disposition	3-2
PATHWAYS AND RECEPTORS	3-3
Air Contamination	3-3
Surface and Groundwater Contamination	3-3
Direct Contact	3-7
SECTION 4: CONCLUSIONS AND RECOMMENDATIONS	4-1
SECTION 5: REFERENCES	5-1
APPENDIX A: COMPLETED EPA FORM T-2070-2 (10-79).	A-1
APPENDIX B: SAMPLING RESULTS	B-1

FIGURES

	<u>Page</u>
FIGURE 1: SITE LOCATION	2-2
FIGURE 2: SITE SKETCH	2-4

TABLES

	<u>Page</u>
TABLE 1: QUINAPOXET RIVER ANALYSIS.	3-4
TABLE 2: GROUNDWATER MONITORING WELL ANALYSIS	3-8

SECTION 1 - INTRODUCTION

1.1 PURPOSE OF INSPECTION

Officials of the Massachusetts Department of Environmental Quality Engineering (DEQE) together with representatives of the Region I EPA Office of Uncontrolled Waste Sites have selected the Holden Site for further evaluation. This evaluation is in preparation for future studies and/or actions that may be implemented under the auspices of the EPA with funds provided by the Hazardous Waste Containment Act of 1980. Ecology and Environment's (E & E) Region I Field Investigation Team was tasked by EPA to perform a Preliminary Assessment of the Holden Landfill under Technical Direction Document (TDD) No. F1-8109-04. A preliminary assessment represents the first phase of an investigation which may lead to site-specific recommendations.

The purpose of this assessment is to organize and evaluate existing information on the Holden Landfill, most of which is contained in Region I EPA files; to make an evaluation of the immediate or long term human and environmental effects of the Landfill, to recommend emergency measures if necessary; and to recommend further action to study and characterize the site.

1.2 OBJECTIVE

The objectives of this assessment were to obtain information about the Holden Site, to discuss any associated hazards, and to present conclusions and recommendations. The E & E report is presented as follows: Site Background includes a general description of the site; a discussion of activities at the site and a site history. Hazards Alleged and/or Identified describes suspected types, amounts and sources of wastes at the site and discusses people or environments at risk in the area and the pathways by which contamination could reach them. The final section of the report discusses Conclusions and Recommendations. A completed EPA Form 2070-2 (10-79) "Potential Hazardous Waste Site Identification and Preliminary Assessment" is also included in Appendix A.

SECTION 2 - SITE BACKGROUND

2.1 SITE DESCRIPTION

The Holden Site is situated in the Town of Holden, Massachusetts in a sparsely populated and wooded area off Wachusett River Street. It can be located on the United State Geological Survey (USGS) 15 Minute Sterling Massachusetts Quadrangle at the approximate coordinates of 42° 22' 40" North and 71° 49' 20" West (Figure 1). The Holden Town Dump (HTD) occupies part of the site.

The Holden Site covers approximately 60 acres and is bounded on the north by the Quinapoxet River, on the west by a wooded area, on the south by Wachusett River Street and on the east by the construction of Interstate I-190. The site consists of the HTD, a small pond and several groundwater leachate seeps/streams. The HTD can be reached via an access road from Wachusett River Street located 2000 feet east of the intersection of Harris Street and Wachusett River Street. Both the pond and HTD are located in the southern section of the site at an elevation of approximately 590 feet above mean sea level (MSL). The pond and HTD are situated approximately 1500 feet away from the Quinapoxet River which is at an elevation of approximately 460 feet above MSL. Surface water flow from the HTD/Pond area would flow either to the north towards the Quinapoxet River or to the south across the Wachusett River Road to an unnamed brook which is tributary to the Quinapoxet River. Two ridges at approximate elevations of 600 feet above MSL are located along the east and west boundaries of the site. A low lying swampy area exists east of the eastern boundary ridge of the site. The leachate seeps are located in the northern section of the site along the steep embankment (28 percent slope) leading down to the Quinapoxet River.





FIGURE 1: HOLDEN SITE LOCATION
 From U.S.G.S. Sterling
 Quadrangle, 15 min. Series
 Scale 1:25000



2.1 Site Description - continued

There is no town water or sewer in this area; however, there is one well at the entrance to the site which is used for water at the landfill. There are six groundwater monitoring wells on site located to the north of the HTD/Pond. Figure 2 shows an overall sketch of the site, topographical contours, and other characteristics. The Quinapoxet River is the main tributary to the Wachusett Reservoir which is located less than 1.5 miles downstream from the site along the Quinapoxet River. The Wachusett Reservoir is part of the Metropolitan District Commission System which supplies drinking water to approximately 2,000,000 people in the metropolitan Boston area.

2.2 SITE ACTIVITY

The site of the fifteen-acre HTD was formerly a sand and gravel operation. The HTD has been in operation since 1959 and was approximately two-thirds full by 1980. The Town of Holden Engineering Division is presently preparing plans for diversion of surface flow around the completed and working faces of the landfill.(1)

2.3 SITE HISTORY

The history of the site as presented here is based on review of EPA correspondence, memoranda, analytical results and other information contained in the EPA files.


The following chronology has been assembled from available information:

1980

02-20-EPA environmental monitor on Interstate I-190 in Holden observed leachate entering Quinapoxet River and informed EPA Enforcement Division to determine if there is a violation of the Clean Water Act.

03/14-EPA received water samples collected from Quinapoxet River and Muddy Brook.

04/09-EPA performed purgeable organic analyses on samples and detected levels greater than 600 ppb of 1,1,1-trichloroethane in the Quinapoxet River sample.



2.3 Site History - continued

1980

05/02-EPA site investigation of the Holden Site in response to state of Massachusetts request regarding applicability of Federal funds to clean up observed leachate streams. EPA took several surface water samples at the Holden Town Dump (HTD) site.

05/07-EPA purgeable organic analysis of HTD surface water samples showed presence of 1,1,1-trichloroethane, toluene, ethylbenzene, benzene and 1,1-dichloroethane.

05/08-EPA was quoted in the Worcester, Massachusetts Evening Gazette as stating that the Quinapoxet River is free of significant chemical pollution and that it has not been determined whether the chemicals are leaching from the HTD.

05/20-EPA extractable organic analysis of HTD surface water samples showed presence of cresol isomers, di-n-ethylphthalate and several unidentified organic acids.

11/01-11/30-Six groundwater monitoring wells installed by State of Massachusetts to confirm or rule out Town of Holden landfill as the source of leachate.

-EPA constructed two leachate control structures

12/18-DEQE requested EPA assistance in sampling and analysis of six groundwater monitoring wells.

1981

01/28-EPA sampling and analyses of the six groundwater monitoring wells at the HTD showed the presence of 1,1-dichloroethane, 1,1,1-trichloroethane, benzene, toluene, ethylbenzene and others.

02/01-Emergency Action Plan for Holden Town Dump (HTD) submitted by EPA/OHM. The Plan stated that because of the limited number of observation wells, it has not been proven beyond a reasonable doubt that the landfill is the source of the contaminated leachate. The Plan recommended hiring of a hydrogeological consultant to determine the groundwater flow pattern in the area, to define extent of contamination and to verify HTD as the source. It also recommended periodic monitoring of groundwater wells and leachate.

03/24-EPA requested that the Massachusetts Department of Public Works (DPW) have a consultant review the effects that the proposed Interstate I-190 Quinapoxet River crossing might have on the leachate problem from the nearby HTD.

04/06-EPA site visit to the HTD.

2.3 Site History - continued

1981

04/16-EPA concluded that the measured depth to water in the existing State wells, their geographic position and site topography all support the conclusion that groundwater and leachate flow from the HTD toward the Quinapoxet River. EPA recommended that existing groundwater monitoring wells be surveyed and the depths to water measured. EPA also recommends weekly sampling and analysis of the groundwater monitoring wells and selected surface water locations for a duration of one month.

04/23-DPW responded to EPA with a consultant's evaluation of the HTD leachate problem and the proximity of the Interstate I-190 crossing construction. The consultant stated that the bridge crossing construction should not interfere with the path of the leachate flow and if any leachate was found in the groundwater during bridge foundation construction, it would be pumped to the construction impoundment area for disposal through sand filters.

05/01-DEQE notified the Town of Holden that it is in violation of Regulations for the Disposal of Solid Waste by Sanitary Landfill and the Drinking Water Regulations as a result of leachate contamination generated by the HTD.

05/12-EPA proposed two rounds (Rounds I and II) of surface and groundwater sampling and priority pollutant analysis at 18 sampling stations (groundwater, surface water and leachate seeps) to determine the presence, concentration and identity of material leaching from the HTD. EPA stated that additional groundwater monitoring wells would be required to determine the areal and vertical extent of any leachate plume.

06/09-DEQE informed DPW that it is still concerned that Interstate I-190 construction activities could alter the flow of leachate from the HTD and adversely affect the Quinapoxet River and therefore requested a meeting with the DPW for further discussions.

06/17-EPA Surveillance and Analysis Branch collected Round I samples from the HTD site and measured the depths to groundwater.

07/23-Round I analytical results showed presence of 1,1-dichloroethane, trans-1,2-dichloroethylene, vinyl chloride, benzene, toluene, ethylbenzene, dioxane, xylenes, and methyl isobutyl ketone at some of the sampling locations.

08/04-Holden responded to the DEQE that it will take action to study the possibility that the HTD is a source of low level leachate contamination. This action will include a topographic survey of the HTD, periodic groundwater sampling and the preparation of a drainage and sealing plan for the HTD.

2.3 Site History - continued

1981

08/14-EPA proposed the installation of additional monitoring wells at the HTD site. These wells include one upgradient well, two downgradient wells located to the north of the HTD to replace four existing steel-cased state wells which are inadequately top sealed and improperly developed, and five additional downgradient wells to define the lateral extent of the contaminant plume and to assess attenuation and retardation of the contaminants.

08/18-EPA informed the DEQE Commissioner that there is no disagreement regarding HTD being the source of contamination discovered in leachate breakouts near the Quinapoxet River.

11/03-EPA performed additional sampling and analysis at the HTD (Monitoring Wells #2 and 5, leachate breakouts). This sampling confirmed presence of contaminants found in Round I sampling and also included the presence of 1,1,1-trichloroethane. The Wachusett Reservoir and Quinapoxet River were also sampled. The Wachusett Reservoir sample showed less than 0.5 ppb toluene.

11/23-Ecology and Environment, Inc. performed a perimeter site survey of the HTD.

2.4 SITE GEOLOGY/HYDROGEOLOGY

The geology and hydrogeology of the site as presented below are based upon a review of EPA correspondence, a Final Environmental Impact Report for Interstate I-190 (2), a Water Resources Study of the Nashua and Souhegan River Basins (3), on-site groundwater monitoring well logs and information provided to FIT by the Department of Public Works in a Proposed Compliance Plan for the Holden Sanitary Landfill (5).

The site is located in a depression between two north-south trending hills. It is bounded on the east and west by the two hills, on the north by the Quinapoxet River and on the south by a gentle slope that leads to Wachusett River Street.

The site is generally underlain by dense granular soil lying on bedrock. The thickness of the overburden ranges from 40 to 90 feet (2).

2.4 Site Geology/Hydrogeology - continued

The surficial deposits on the site are composed of stratified and sorted (glaciofluvial) deposits of sand, gravel, silt and clay (3), overlying a discontinuous layer of till (2, 4). The glaciofluvial deposits are characteristically a loose, brown to tan well-graded material. The till is a dense gray silt and gravelly sand with boulders (2).

The bedrock is composed of metamorphic units. The predominant formations are composed of mica schist, chlorite schist and phyllite, interbedded with micaceous quartzite. The mica content in these formations gives the bedrock a significantly fissile nature, that is, the bedrock is fractured along parallel planes of weakness. Irregular fractures and small faults are also present in the bedrock (2). Predominant strike and dip directions of these features are unknown. Subsurface bedrock topography is also unknown, because of a lack of geophysical data for the site.

Detailed hydrogeologic data for the site is not available. However, a review of the previously mentioned references allows the following hydrogeologic conclusions to be drawn.

1. Static water level measurements taken on 17 June 1981 by EPA in monitoring wells 1 through 6 indicate a hydraulic gradient sloping northeast from the disposal site toward the Quinapoxet River. Groundwater originating on the site is likely to be recharging the River in this area.
2. Surface topography suggests that there may be subsurface hydraulic connections between the site and the intermittent stream to the south, the pond to the west and a swamp area adjacent to Route I-190. However, lack of hydrologic data in these areas prevents verification of groundwater movement in these directions.
3. Static water level measurements taken in 1972 and 1974 by the Engineering Department of the Town of Holden (5) revealed that water levels were higher in the pond west of the site than in test borings and pits on the landfill. These data suggest that the pond may be "perched" above the regional water table and may not be hydrologically connected with groundwater movement under the site.

2.4 Site Geology/Hydrogeology - continued

4. Well yields for the unconsolidated and bedrock aquifers are as follows: (3)

-- Glaciofluvial Deposits	0-100 gal/min.
-- Till	0-10 gal/min.
-- Bedrock	0-10 gal/min.

EPA has proposed the installation of eight additional groundwater monitoring wells at the Holden Site. One of these wells would serve as an upgradient well, to be located south of the HTD replacing the HTD well for sampling purposes. Two wells are proposed to replace the State - installed wells located north of the HTD. Five additional groundwater monitoring wells are proposed by EPA to locate the vertical extent of a contaminant plume as it may travel towards the Quinapoxet River. EPA has also proposed that an electrical resistivity subsurface investigation be performed in the area between the HTD and the Quinapoxet River. This study, to be performed in advance of the groundwater monitoring well program, also seeks information on the lateral contaminant plume movement as well as any information on stratigraphy and bedrock features.

SECTION 3 - HAZARDS ALLEGED AND/OR IDENTIFIED

3.1 WASTE CHARACTERISTICS

3.1.1 TYPES AND QUANTITIES

No data exist which characterize the wastes which have been discarded at the HTD. The HTD was developed to receive mixed municipal refuse, however, some industrial waste may have been disposed of in the landfill (6).

The majority of industrial waste brought to the HTD comes from three sources within the Town of Holden (6). These sources are 1) Electronics Controls Corporation which manufactures printed circuit boards, 2) Reed Rolled Thread & Die Company, a tool and machine die manufacturer, and 3) Reid Plastics Corporation which manufactures plastic products. At one time industrial sludge was hauled from Presmet-GKN Power Met., Inc., a screw manufacturing facility, and disposed at the landfill site. This material is no longer brought to the HTD. It has also been reported that Reed Rolled Thread & Die Company may also have disposed a sludge material at the HTD (7). Other industrial wastes landfilled at the HTD consist mainly of paper products and small empty waste containers.

Some refuse was also deposited in the pond located immediately west of the HTD. Tires have been visible along the edge of the pond (7). Purgeable organic analysis of a water sample from the pond indicated no detectable contamination. The analytical results may be found in Appendix A. Several leachate breakouts have been observed at the ground surface north of the HTD on the steep slope which leads down to the Quinapoxet River. Some of these leachate breakouts form several small streams have been stained a yellow-orange color.

3.1 Waste Characteristics - continued

It has been estimated that flow from the major breakout named "Red Brook," can be up to 10 gallons/minute (7). This leachate at times has been described as foamy, whitish-colored with a pronounced odor (7). Other leachate streams which were observed on site flowing towards the Quinapoxet River exhibited flows of only 1-2 gallons/minute.

3.1.2 WASTE MANAGEMENT/DISPOSITION

Open dumping commenced in 1959 on property owned by the Town of Holden and known as HTD. In 1970, plans were developed by a consultant to the Town of Holden to operate and develop the HTD as a sanitary landfill using a cut and fill landfilling technique. The landfill is located in an area previously used for sand and gravel mining. Site security consists of a locked gate on the access road located immediately south of the HTD. The sides of the access road are also fenced. The landfill site contains a maintenance building/storage shed for landfill equipment. Water for sanitary facilities and vehicle washing is provided by an on-site well.

The HTD was cited on 1 May 1981 by the DEQE for violations of 1) the regulations for the disposal of solid waste by sanitary landfill and 2) drinking water regulations. On 4 August 1981, the Town of Holden proposed a voluntary compliance plan to serve in place of a formal compliance order which would have been issued by the DEQE. This plan consisted of a topographic survey of the HTD, and design of surface flow diversion for the completed face of the HTD. The topographic survey of the HTD is estimated to be completed by December 1981. Final impervious soil cover is being purchased for the completed portions of the HTD (approximately 30-40% of the total available landfill area) in order to prevent any surface water infiltration as outlined above.

3.1 Waste Management/Disposition - continued

It has been estimated that landfilling capacity at the HTD will run out by 1988 (6). The HTD receives mixed municipal refuse/ industrial waste between 10 a.m. and 4 p.m. five days per week. There are no weighing scales for truck delivery, however, the Town of Holden has performed two surveys in 1975 and 1979 to quantify the amount of landfill volume which is still available for waste disposal. In 1975, 240.20 acre-feet were available for landfilling whereas in 1979 only 62.75 acre-feet remained available (6).

3.2 PATHWAYS AND RECEPTORS

3.2.1 Air Contamination

Ambient air monitoring for organic vapors has not been conducted at the Holden site. However, EPA Investigators have detected pronounced odors in the vicinity of the leachate breakouts north of the HTD on site inspections in May 1980 and April 1981.

3.2.2 Surface and Groundwater Contamination

Surface water from the HTD may flow off-site in a southerly direction, eventually draining into the Quinapoxet River. Surface water from the HTD can also flow in a northerly direction off-site down a steep embankment and into the Quinapoxet River downstream from the previously described surface flow discharge location. The Quinapoxet River at this point is located approximately one and one-quarter mile from its discharge into the Wachusett Reservoir, which is a drinking water supply for the Boston metropolitan area. There are two surface water features on site which include a small pond located adjacent and to the west of the HTD and a series of groundwater leachate breakouts, north of the HTD, some of which form small leachate streams.

Surface water at various locations on and off site has been sampled and analyzed. Results of purgeable organic analysis on samples taken from the Quinapoxet River at the confluence with the HTD leachate stream (Red Brook) are presented in Table 1. Concentrations of contaminants was determined only for the priority pollutants listed in Table 1.

TABLE 1

Quinapoxet River Analysis

<u>March 1980</u>		<u>May 1980</u>	
<u>Compound</u>	<u>Approx. Conc. (ppb)</u>	<u>Compound</u>	<u>Approx. Conc. (ppb)</u>
Dichloro-fluoro-methane*		acetone*	
Acetone*		methyl ethyl ketone*	
Isopropyl Alcohol*		methyl isobutyl ketone*	
1,1-dichloroethane	100	Isopropyl alcohol*	
1,1-dichloroethylene	10	1,1,1-trichloroethane	1
trans-1,2-dichloroethylene	20		
methyl ethyl ketone*			
1,1,1-trichloroethane	L600		
trichloroethylene	1		
benzene	4		
methyl methacrylate*			
methyl isobutyl ketone*			
toluene	30		
ethylbenzene	3		
tetrachloroethylene	2		

* = non-priority pollutant, therefore not quantified

L = greater than

3.2 Pathways and Receptors - continued

In May 1980 additional surface water samples were taken for purgeable organic analysis from the Quinapoxet River upstream from the HTD site as well as from the on-site pond located immediately west of the HTD. No volatile organic compounds were detected in these samples. Additional surface water samples were collected in July 1981 for purgeable organic analysis. Results of this analysis are presented in Appendix B; however, no contaminants were detected in the surface water of the pond (reference No. L005) or the Quinapoxet River (reference Nos. 001, 002) both upstream and immediately downstream of the site. Furthermore, no contaminants were detected from limited surface water sampling in the Quinapoxet river conducted again in November 1981.

The groundwater leachate breakouts, located north of the HTD near the Quinapoxet River were also sampled and analyzed in July and November 1981. The main leachate stream was sampled at several locations upstream from the Quinapoxet River. Purgeable volatile organic analysis results showed in part the presence of the following compounds:

	<u>Concentration Range (ppb)</u>
1,1-dichloroethane	1.1 - 59
trans-1,2-dichloroethylene	9 - 16
1,1,1-trichloroethane	trace - 65
toluene	trace - 11
ethylbenzene	0 - 3
xylenes	0 - 8

These compounds, however, were not detected in the main leachate stream prior to entering the Quinapoxet River. (See Appendix B, reference Nos. L1A, L1B and L1C, for analytical results and Figure 2 for sampling locations)

Other leachate streams which enter the Quinapoxet River 200 to 500 feet upstream of the main leachate stream were sampled prior to entering the Quinapoxet River. The analysis of samples taken in July 1981 (Appendix B, Reference Nos. L02, L03, L04, L05) detected no volatile organic compounds except 220 ppb of dioxane

3.2 Pathways and Receptors - continued

in the leachate stream which enters the Quinapoxet River 500 feet upstream from the main leachate stream. Analysis of samples taken in November 1981 from the other leachate streams showed in part the presence of the following compounds:

	<u>Concentration Ranges (ppb)</u>
1,1-dichloroethane	19 - 210
1,1,1-trichloroethane	2.6 - 240
toluene	1.7 - 21
1,2-dichloroethylene	3.8 - 21
1,2-dichloroethane	1.2 - 21
vinyl chloride	17 - 190

A conclusion can be made from observation of the analytical results on the leachate breakouts and other surface waters that there is a tremendous variation of contaminant concentrations detected at various sampling times. The presence/absence of certain contaminants at different sampling times particularly in the leachate breakouts also confirms this variability.

Available analytical data indicate that the Wachusett Reservoir, which is fed by the Quinapoxet River, was sampled only in May 1980 and November 1981. No contaminants were detected in 1980, however, less than 0.5 ppb of toluene was detected in 1981.

Settling ponds are to be constructed at the Route I-190/Quinapoxet River Bridge crossing construction site which is located to the east of the site. Groundwater removed during the bridge abutment foundation construction will be pumped into these settling ponds.

Six groundwater monitoring wells were installed on site by the State of Massachusetts in November 1980. These wells, all located between the HTD and the Quinapoxet River, were not properly constructed or adequately secured (8). There is also a well on site used to supply water for the HTD equipment.

3.2 Pathways and Receptors - continued

Purgeable volatile organic analysis of the on-site well did not detect any volatile organic compounds. Table 2 presents a partial list of the volatile organics detected during sampling/analysis of the six groundwater monitoring wells. Locations of these wells are plotted on Figure 2.

Comparison of the analytical data presented in this section indicates that the same contaminants are present in the groundwater north of the HTD, the leachate breakouts north of the HTD and the Quinapoxet River.

3.2.3 Direct Contact

Limited sampling/analysis of the groundwater leachate breakouts/streams located north of the HTD indicates that the site does not presently constitute a direct contact health hazard. Vehicular access is limited at the HTD from the southern site access road; however, access by foot can be gained to the site along its boundaries. A full site inspection combined with further monitoring of surface water and leachate as well as the landfill closure techniques will determine more conclusively if there is any potential on site for direct exposure to any hazardous and toxic chemicals.

TABLE 2

Groundwater Monitoring Well Analyses (ppb)

Holden, Massachusetts

1 9 8 1

	#1*	#2			#3		#4		#5			#6	
	01/28	01/28	07/23	11/03	01/28	07/23	01/28	07/23	01/28	07/23	11/03	01/28	07/23
1,1-dichloroethane	159	ND	ND	ND	ND	1	5	3	12	ND	8.4	9	4
trans-1,2-dichloroethylene	34	42	25	17	40	6	15	16	16	ND	3.4	108	32
1,1,1-trichloroethane	298	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	15	1
benzene	12	12	9	2.3	10	9	8	3	20	1	16	7	6
toluene	114	85	67	61	102	62	4	2	120	60	98	17	12
ethylbenzene	18	17	8	16	13	13	12	1	35	30	25	2	7
vinyl chloride	ND	ND	100	190	ND	18	ND	34	ND	58	250	ND	21
xylene	ND	ND	50	30	ND	26	ND	3	ND	110	50	ND	17
dioxane	ND	ND	ND	ND	ND	ND	ND	ND	ND	138	ND	ND	ND

* = Well #1 was dry on 7/23/81 therefore no sample collected.

SECTION 4 - CONCLUSIONS AND RECOMMENDATIONS

This preliminary assessment summarizes available information on the HTD site history and the results of sampling/analysis of both surface water and groundwater suspected of being contaminated by the HTD facility. This assessment raises two issues regarding the site which should be addressed. These issues are:

In the short term,

1. Does the site possess the potential for any immediate health effects from either possible contamination of the MDC Wachusett Reservoir, (via the Quinapoxet River), or I-190 Bridge Crossing construction activities where potentially contaminated groundwater must be pumped to manmade surface impoundments, or direct contact with leachate streams and other surface water on site?

In the long term,

2. What is the extent of groundwater/bedrock contamination on and off site, can the leachate flow(s) be fully characterized as to quantity/quality (remedial options), and what effects will future HTD operations have on surface water/groundwater contamination?

The following recommendations are presented in the order in which they should be executed. The purpose of these recommendations is to fill in the gaps in information currently available regarding the site and the three contaminant pathways - air, surface water and groundwater. It also seeks to gather analytical data on a more continuous basis to better characterize the contaminants and their concentrations.

1. Perform site inspection and use a portable organic vapor analyzer to characterize area of leachate breakouts (air pathway).
2. Site inspection should also include sampling/OVA analysis of Wachusett Reservoir, Quinapoxet River downstream, HTD Pond and off-site surface water to the east and south of the site (surface water pathway).
3. Review activities of construction personnel in regard to contact with and disposal of any contaminated groundwater resulting from bridge abutment construction procedures (groundwater pathway).

Section 4 - Conclusions and Recommendations - continued

4. Review existing HTD closure plans and operations with regard to minimizing/avoiding further site contamination (all pathways)
5. Monitor leachate breakouts, HTD Pond, Quinapoxet River and the Wachusett Reservoir on a continuous basis (i.e. monthly) to more accurately assess the surface water contamination which exists based on past random limited surface water sampling, the results of which were extremely variable.
6. Survey remaining areas of the site in addition to those areas currently being completed by the Town of Holden. The purpose of the survey is to produce a topographical base site map (1" = 100') with existing manmade features such as dirt roads, boundaries, power lines, surface water, existing wells, etc. This map will cover the area bounded by Wachusett River Street to the south and east, the Quinapoxet River to the north and along the west side of the HTD Pond. It will be used to develop further site investigatory work (i.e. subsurface geophysical, groundwater monitoring wells)
7. Perform a full field investigation which includes an electrical resistivity (ER) subsurface site investigation for all areas surrounding the HTD to assess potential horizontal contaminant plume migration from the HTD and to also determine groundwater/bedrock profiles. The profiles will be used to understand the complete hydrogeology of the site and how it effects the on-site pond and leachate breakouts.
8. Measure surface water and groundwater table elevations concurrently with ER study.
9. Perform a seismic refraction study on site as needed to verify and/or determine bedrock/groundwater contours.
10. Submit Interim Field Investigation report.
11. Develop and implement groundwater well monitoring program to assess full aquifer and bedrock contamination (vertical migration) and to allow continuous monitoring of horizontal plume migration.
12. Sampling/analysis of groundwater monitoring wells.
13. Quantify leachate flow into the Quinapoxet River.
14. Review future plans by the Town of Holden for the HTD.
15. Complete field investigation report.

Recommendations 1, 2, 3 and 4 are intended for short term study and investigation whereas items 5 through 15 will require considerably more time, planning and effort and seek to gather data necessary for any long term remedial options.

SECTION 5 - REFERENCES

1. Letter. Allan R. Berg, Town Engineer, Holden, Massachusetts to Gilbert T. Joly, DEQE, Worcester, Massachusetts dated 4 August 1981.
2. Final Environmental Impact Report for Interstate I-190, Massachusetts Department of Public Works. 1974.
3. Bradley, R. A., and B. P. Hansen, Water Resources of the Nashua and Souhegan River Basins, Massachusetts, U.S. Geological Survey Atlas AA-279.
4. Well Logs for Wells No. 1 through 6 compiled by R. E. Chapman Company, Oakdale, Massachusetts. November 1980.
5. Letter. Winston E. Fox, Town Surveyor, Holden, Massachusetts to Gilbert T. Joly, DEQE, Worcester, Massachusetts dated 19 November 1981.
6. Telecon. Hagger, Christopher, Ecology and Environment, Inc. with Alan Berg, Holden Town Engineer, 3 November 1981. Discussion of Site History and Waste Characteristics.
7. Memo. Stephen Mangion, Geologist, EPA Waste Management Branch to John Hackler, Chief EPA Office of Uncontrolled Waste Sites dated 16 April 1981. Trip report for site visit to Holden Town Landfill.
8. Memo. Stephen Mangion, Geologist EPA Waste Management Branch to John Hackler, Chief EPA Office of Uncontrolled Waste Sites dated 14 August 1981. Additional Monitoring Wells at the Holden Town Dump.

APPENDIX A



POTENTIAL HAZARDOUS WASTE SITE
IDENTIFICATION AND PRELIMINARY ASSESSMENT

REGION SITE NUMBER (to be assigned by HQ)

NOTE: This form is completed for each potential hazardous waste site to help set priorities for site inspection. The information submitted on this form is based on available records and may be updated on subsequent forms as a result of additional inquiries and on-site inspections.

GENERAL INSTRUCTIONS: Complete Sections I and III through X as completely as possible before Section II (Preliminary Assessment). File this form in the Regional Hazardous Waste Log File and submit a copy to: U.S. Environmental Protection Agency; Site Tracking System; Hazardous Waste Enforcement Task Force (EN-335); 401 M St., SW; Washington, DC 20460.

I. SITE IDENTIFICATION

A. SITE NAME <u>HOLDEN TOWN DUMP</u>		B. STREET (or other identifier) <u>HARRIS STREET</u>	
C. CITY <u>HOLDEN MA</u>	D. STATE <u>MASS</u>	E. ZIP CODE <u>01520</u>	F. COUNTY NAME <u>WORCESTER</u>
G. OWNER/OPERATOR (if known) 1. NAME <u>Town of Holden</u>		2. TELEPHONE NUMBER	
H. TYPE OF OWNERSHIP <input type="checkbox"/> 1. FEDERAL <input type="checkbox"/> 2. STATE <input type="checkbox"/> 3. COUNTY <input checked="" type="checkbox"/> 4. MUNICIPAL <input type="checkbox"/> 5. PRIVATE <input type="checkbox"/> 6. UNKNOWN			

I. SITE DESCRIPTION

Municipal Dump

J. HOW IDENTIFIED (i.e., citizen's complaint, OSHA citations, etc.)

EPA - John Hackler

K. DATE IDENTIFIED
(mo., day, & yr.)

5/1/80

L. PRINCIPAL STATE CONTACT

1. NAME

SABIN LOND

MA DWP (EAST)

2. TELEPHONE NUMBER

617 726-6373

II. PRELIMINARY ASSESSMENT (complete this section last)

A. APPARENT SERIOUSNESS OF PROBLEM

☒ 1. HIGH ☐ 2. MEDIUM ☐ 3. LOW ☐ 4. NONE ☐ 5. UNKNOWN

RECOMMENDATION

☐ 1. NO ACTION NEEDED (no hazard)

☐ 2. IMMEDIATE SITE INSPECTION NEEDED
a. TENTATIVELY SCHEDULED FOR:

b. WILL BE PERFORMED BY:

☒ 3. SITE INSPECTION NEEDED

a. TENTATIVELY SCHEDULED FOR:

2 MAY 1980

b. WILL BE PERFORMED BY:

DAVID W. TORPOTT

☐ 4. SITE INSPECTION NEEDED (low priority)

C. PREPARER INFORMATION

1. NAME

David W. Torpott

2. TELEPHONE NUMBER

617/223-7265

3. DATE (mo., day, & yr.)

5/29/80

III. SITE INFORMATION

A. SITE STATUS

☒ 1. ACTIVE (Those industrial or municipal sites which are being used for waste treatment, storage, or disposal on a continuing basis, even if infrequently.)

☐ 2. INACTIVE (Those sites which no longer receive wastes.)

☐ 3. OTHER (specify):
(Those sites that include such incidents like "midnight dumping" where no regular or continuing use of the site for waste disposal has occurred.)

B. IS GENERATOR ON SITE?

☒ 1. NO

☐ 2. YES (specify generator's four-digit SIC Code):

AREA OF SITE (in acres)

1.5

D. IF APPARENT SERIOUSNESS OF SITE IS HIGH, SPECIFY COORDINATES

1. LATITUDE (deg.-min.-sec.)

42° 22' 40.3N

2. LONGITUDE (deg.-min.-sec.)

71° 49' 16.9W

E. ARE THERE BUILDINGS ON THE SITE?

☐ 1. NO

☒ 2. YES (specify):

recycled paper

BACK FOR PAYLOADER

A. TRANSPORTER		B. STORER		C. TREATMENT		D. DISPOSER	
<input checked="" type="checkbox"/> 1. RAIL		<input checked="" type="checkbox"/> 1. F		<input checked="" type="checkbox"/> 1. FILTRATION		<input checked="" type="checkbox"/> 1. LANDFILL	
<input type="checkbox"/> 2. SHIP		<input type="checkbox"/> 2. SURFACE IMPOUNDMENT		<input type="checkbox"/> 2. INCINERATION		<input type="checkbox"/> 2. LANDFARM	
<input type="checkbox"/> 3. BARGE		<input type="checkbox"/> 3. DRUMS		<input type="checkbox"/> 3. VOLUME REDUCTION		<input type="checkbox"/> 3. OPEN DUMP	
<input checked="" type="checkbox"/> 4. TRUCK		<input type="checkbox"/> 4. TANK, ABOVE GROUND		<input type="checkbox"/> 4. RECYCLING/RECOVERY		<input type="checkbox"/> 4. SURFACE IMPOUNDMENT	
<input type="checkbox"/> 5. PIPELINE		<input type="checkbox"/> 5. TANK, BELOW GROUND		<input type="checkbox"/> 5. CHEM./PHYS. TREATMENT		<input type="checkbox"/> 5. MIDNIGHT DUMPING	
<input type="checkbox"/> 6. OTHER (specify):		<input checked="" type="checkbox"/> 6. OTHER (specify): LOOSE MATERIAL UNDER DIRT		<input type="checkbox"/> 6. BIOLOGICAL TREATMENT		<input type="checkbox"/> 6. INCINERATION	
				<input type="checkbox"/> 7. WASTE OIL REPROCESSING		<input type="checkbox"/> 7. UNDERGROUND INJECTION	
				<input type="checkbox"/> 8. SOLVENT RECOVERY		<input type="checkbox"/> 8. OTHER (specify):	
				<input type="checkbox"/> 9. OTHER (specify): SANITARY LANDFILL			

E. SPECIFY DETAILS OF SITE ACTIVITIES AS NEEDED

SITE IS A MUNICIPAL LANDFILL

A. WASTE TYPE

V. WASTE RELATED INFORMATION

☒ 1. UNKNOWN ☐ 2. LIQUID ☐ 3. SOLID ☐ 4. SLUDGE ☐ 5. GAS

B. WASTE CHARACTERISTICS

☒ 1. UNKNOWN ☐ 2. CORROSIVE ☐ 3. IGNITABLE ☐ 4. RADIOACTIVE ☐ 5. HIGHLY VOLATILE
☐ 6. TOXIC ☐ 7. REACTIVE ☐ 8. INERT ☐ 9. FLAMMABLE

☐ 10. OTHER (specify):

C. WASTE CATEGORIES

1. Are records of wastes available? Specify items such as manifests, inventories, etc. below.

NO

2. Estimate the amount (specify unit of measure) of waste by category; mark 'X' to indicate which wastes are present.

a. SLUDGE		b. OIL		c. SOLVENTS		d. CHEMICALS		e. SOLIDS		f. OTHER	
AMOUNT	UNIT OF MEASURE	AMOUNT	UNIT OF MEASURE	AMOUNT	UNIT OF MEASURE	AMOUNT	UNIT OF MEASURE	AMOUNT	UNIT OF MEASURE	AMOUNT	UNIT OF MEASURE
UNKNOWN		UNKNOWN		UNKNOWN		UNKNOWN		UNKNOWN		UNKNOWN	
(1) PAINT, PIGMENTS		(1) DILY WASTES		(1) HALOGENATED SOLVENTS		(1) ACIDS		(1) FLYASH		(1) LABORATORY PHARMACEUT.	
(2) METALS SLUDGES		(2) OTHER (specify):		(2) NON-HALOGENATED SOLVENTS		(2) PICKLING LIQUORS		(2) ASBESTOS		(2) HOSPITAL	
(3) POTW				(3) OTHER (specify):		(3) CAUSTICS		(3) MILLING/ MINE TAILINGS		(3) RADIOACTIVE	
(4) ALUMINUM SLUDGE						(4) PESTICIDES		(4) FERROUS SMLTG. WASTES		(4) MUNICIPAL	
(5) OTHER (specify):						(5) DYES/INKS		(5) NON-FERROUS SMLTG. WASTES		(5) OTHER (specify):	
						(6) CYANIDE		(6) OTHER (specify):			
						(7) PHENOLS					
						(8) HALOGENS					
						(9) PCB					
						(10) METALS					
						(11) OTHER (specify):					

WASTE RELATED INFORMATION (cont.)

A LIST SUBSTANCES OF GREATEST CONCERN WHICH MAY BE ON THE SITE (place in descending order of hazard).

Trichloroethane
Trichloroethylene
Benzene
Toluene
Cresol

Ethyl Benzene

4. ADDITIONAL COMMENTS OR NARRATIVE DESCRIPTION OF SITUATION KNOWN OR REPORTED TO EXIST AT THE SITE.

Actual Discharge. Site is on
DPW Property - Not The Dump

VI. HAZARD DESCRIPTION

A. TYPE OF HAZARD.	B. POTENTIAL HAZARD (mark 'X')	C. ALLEGED INCIDENT (mark 'X')	D. DATE OF INCIDENT (mo., day, yr.)	E. REMARKS
1. NO HAZARD				
2. HUMAN HEALTH	✓			
3. NON-WORKER INJURY/EXPOSURE	✓			
4. WORKER INJURY				
5. CONTAMINATION OF WATER SUPPLY	✓			
6. CONTAMINATION OF FOOD CHAIN	✓			
7. CONTAMINATION OF GROUND WATER	✓	✓	2 MAY 80	Ground water is polluting
8. CONTAMINATION OF SURFACE WATER	✓	✓	2 MAY 80	The Quinapoint River
9. DAMAGE TO FLORA/FAUNA	✓			
10. FISH KILL	✓			
11. CONTAMINATION OF AIR	✓	✓	2 MAY 80	Smells like a sewer
12. NOTICEABLE ODORS	✓	✓	2 MAY 80	" " " "
13. CONTAMINATION OF SOIL	✓	✓	2 MAY 80	Red deposit
14. PROPERTY DAMAGE				
15. FIRE OR EXPLOSION				
16. SPILLS/LEAKING CONTAINERS/ RUNOFF/STANDING LIQUIDS				
17. SEWER, STORM DRAIN PROBLEMS				
18. EROSION PROBLEMS				
19. INADEQUATE SECURITY				
20. INCOMPATIBLE WASTES	✓			
21. MIDNIGHT DUMPING	✓			
22. OTHER (specify):				

recycled paper

ecology and environment, inc.

VII. PERMIT INFORMATION

A. INDICATE ALL APPLICABLE PERMITS HELD BY THE SITE.

- ☐ 1. NPDES PERMIT ☐ 2. SPCC PLA. ☐ 3. STATE PERMIT (specify): UNKNOWN
☐ 4. AIR PERMITS ☐ 5. LOCAL PERMIT ☐ 6. RCRA TRANSPORTER
☐ 7. RCRA STORER ☐ 8. RCRA TREATER ☐ 9. RCRA DISPOSER

☐ 10. OTHER (specify):

B. IN COMPLIANCE?

- ☐ 1. YES ☐ 2. NO ☒ 3. UNKNOWN

4. WITH RESPECT TO (list regulation name & number):

VIII. PAST REGULATORY ACTIONS

- ☐ A. NONE ☐ B. YES (summarize below)

unknown

IX. INSPECTION ACTIVITY (past or on-going)

- ☐ A. NONE ☐ B. YES (complete items 1, 2, 3, & 4 below)

1. TYPE OF ACTIVITY	2. DATE OF PAST ACTION (mo., day, & yr.)	3. PERFORMED BY: (EPA/State)	4. DESCRIPTION
<u>unknown</u>			

X. REMEDIAL ACTIVITY (past or on-going)

- ☐ A. NONE ☒ B. YES (complete items 1, 2, 3, & 4 below)

1. TYPE OF ACTIVITY	2. DATE OF PAST ACTION (mo., day, & yr.)	3. PERFORMED BY: (EPA/State)	4. DESCRIPTION
<u>Oil and Grease</u>	<u>27 May 1990</u>	<u>EPA</u>	<u>Filter system installation</u>

NOTE: Based on the information in Sections III through X, fill out the Preliminary Assessment (Section II) information on the first page of this form.

APPENDIX B

PRIORITY POLLUTANT ANALYTICAL RESULTS
GROUNDWATER MONITORING WELL 5' ING

Location: Holden, Mass.
Sampling Date: July 1981

VOLATILES (ug/l)	MONITORING WELL REFERENCE NUMBER(S)			
	W02	W03	W04	W05
acrolein	ND	ND	ND	ND
acrylonitrile	ND	ND	ND	ND
benzene	9	9	3	1
carbon tetrachloride	ND	ND	ND	ND
chlorobenzene	ND	ND	~1	< 30
1,2-dichloroethane	ND	ND	ND	ND
1,1,1-trichloroethane	ND	ND	ND	ND
1,1-dichloroethane	ND	< 1	3	ND
1,1,2-trichloroethane	ND	ND	ND	ND
1,1,2,2-tetrachloroethane	ND	ND	ND	ND
chloroethane	ND	ND	ND	ND
2-chloroethylvinyl ether	ND	ND	ND	ND
chloroform	ND	ND	ND	ND
1,1-dichloroethylene	ND	ND	ND	ND
1,2-trans-dichloroethylene	25	6	16	ND
1,2-dichloropropane	ND	ND	ND	ND
1,3-dichloropropylene	ND	ND	ND	ND
ethylbenzene	8	13	1	30
methylene chloride	ND	ND	ND	1
methyl chloride	ND	ND	ND	ND
methyl bromide	ND	ND	ND	ND
bromoform	ND	ND	ND	ND
dichlorobromomethane	ND	ND	ND	ND
trichlorofluoromethane	ND	ND	ND	ND
dichlorodifluoromethane	ND	ND	ND	ND
chlorodibromomethane	ND	ND	ND	ND
tetrachloroethylene	ND	ND	ND	ND
toluene	67	62	2	60
trichloroethylene	ND	ND	ND	ND
vinyl chloride	100	18	34	58
OTHER: (ug/l)				
xylene	50	26	3	110
dichlorofluoromethane	ND	ND	PRESENT	ND
acetone	ND	ND	ND	ND
isopropanol	ND	ND	ND	ND
methyl ethyl ketone	ND	ND	ND	ND
butanol	ND	ND	ND	ND
C-7 alkane	ND	ND	ND	ND
methyl isobutyl ketone	ND	ND	ND	7
hexanol	ND	ND	ND	ND
C-3 benzene	ND	ND	ND	ND
C-9 alkane	ND	ND	ND	ND
trichlorotrifluoroethane	ND	ND	ND	ND
dichlorotrifluoroethane	ND	ND	ND	ND
C-6 alkane	ND	ND	ND	ND
hexanol	ND	ND	ND	ND
C-8 ketone	ND	ND	ND	ND
aldehyde	ND	ND	ND	ND
tetrahydrofuran	ND	ND	ND	ND
glycol type molecule	PRESENT	PRESENT	ND	ND
camphor	PRESENT	PRESENT	ND	ND
C-10 alkane	PRESENT	PRESENT	ND	PRESENT
chlorofluoromethane	ND	PRESENT	ND	ND
ethyl ether	ND	PRESENT	ND	ND
C-3 alkyl benzene	ND	PRESENT	PRESENT	PRESENT
methyl ethyl sulfide	ND	ND	ND	PRESENT
dioxane	ND	ND	ND	138
methyl isopropyl ketone	ND	ND	ND	PRESENT
dimethyl furan	ND	ND	ND	PRESENT
hexanone	ND	ND	ND	PRESENT
heptanone	ND	ND	ND	PRESENT
large alkanes, LC-10	ND	ND	ND	PRESENT

recycled paper

ecology and environment, inc.

recycled paper

ecology and environment, inc.

ND - Not Detected

PRIORITY POLLUTANT ANALYTICAL ILTS
GROUNDWATER MONITORING WELL SAMPLING

Location: Holden, Mass
Sampling Date: July 1981

VOLATILES (ug/l)	MONITORING WELL REFERENCE NUMBER(S)			
	W06	L1A	L1B	L1C
acrolein	ND	ND	ND	ND
acrylonitrile	ND	ND	ND	ND
benzene	6	ND	ND	ND
carbon tetrachloride	ND	ND	ND	ND
chlorobenzene	27	ND	ND	ND
1,2-dichloroethane	ND	ND	ND	ND
1,1,1-trichloroethane	1	65	55	ND
1,1-dichloroethane	4	59	27	ND
1,1,2-trichloroethane	ND	ND	ND	ND
1,1,2,2-tetrachloroethane	ND	ND	ND	ND
chloroethane	ND	ND	ND	ND
2-chloroethylvinyl ether	ND	ND	ND	ND
chloroform	ND	ND	ND	ND
1,1-dichloroethylene	ND	ND	ND	ND
1,2-trans-dichloroethylene	32	16	9	ND
1,2-dichloropropane	ND	ND	ND	ND
1,3-dichloropropylene	ND	ND	ND	ND
ethylbenzene	7	3	ND	ND
methylene chloride	ND	ND	ND	ND
methyl chloride	ND	ND	ND	ND
methyl bromide	ND	ND	ND	ND
bromoform	ND	ND	ND	ND
dichlorobromomethane	ND	ND	ND	ND
trichlorofluoromethane	ND	ND	ND	ND
dichlorodifluoromethane	ND	ND	ND	ND
chlorodibromomethane	ND	ND	ND	ND
tetrachloroethylene	ND	ND	ND	ND
toluene	12	11	5	ND
trichloroethylene	ND	ND	ND	ND
vinyl chloride	21	ND	ND	ND
OTHER:(ug/l)				
xylene	17	8	ND	ND
dichlorofluoromethane	PRESENT	ND	ND	ND
acetone	ND	ND	ND	PRESENT
isopropanol	ND	ND	ND	ND
methyl ethyl ketone	ND	PRESENT	PRESENT	PRESENT
butanol	ND	ND	ND	ND
C-7 alkane	ND	ND	ND	ND
methyl isobutyl ketone	ND	PRESENT	PRESENT	5
hexanol	ND	ND	ND	ND
C-3 benzene	ND	ND	ND	ND
C-9 alkane	ND	ND	ND	ND
trichlorotrifluoroethane	ND	ND	ND	ND
dichlorotrifluoroethane	ND	ND	ND	ND
C-6 alkane	ND	ND	ND	ND
hexanol	ND	ND	ND	ND
C-8 ketone	ND	ND	ND	ND
aldehyde	ND	ND	ND	ND
tetrahydrofuran	ND	ND	ND	ND
chlorofluoromethane	PRESENT	ND	ND	ND
ethyl ether	PRESENT	ND	ND	ND
glycol type molecule	PRESENT	ND	ND	ND
C-3 alkyl benzene	PRESENT	ND	ND	ND
C-10 alkane	PRESENT	ND	ND	ND
camphor	ND	ND	ND	PRESENT

ND = Not Detected

PRIORITY POLLUTANT ANALYTICAL RESULTS
GROUNDWATER MONITORING WELL SA 1NG

Location: Holden, Mass
Sampling Date: July 1981

VOLATILES (ug/l)	MONITORING WELL REFERENCE NUMBER(S)			
	L02	L03	L04	L005
acrolein	ND	ND	ND	ND
acrylonitrile	ND	ND	ND	ND
benzene	ND	ND	ND	ND
carbon tetrachloride	ND	ND	ND	ND
chlorobenzene	ND	ND	ND	ND
1,2-dichloroethane	ND	ND	ND	ND
1,1,1-trichloroethane	ND	ND	ND	ND
1,1-dichloroethane	ND	ND	ND	ND
1,1,2-trichloroethane	ND	ND	ND	ND
1,1,2,2-tetrachloroethane	ND	ND	ND	ND
chloroethane	ND	ND	ND	ND
2-chloroethylvinyl ether	ND	ND	ND	ND
chloroform	ND	ND	ND	ND
1,1-dichloroethylene	ND	ND	ND	ND
1,2-trans-dichloroethylene	ND	ND	ND	ND
1,2-dichloropropane	ND	ND	ND	ND
1,3-dichloropropylene	ND	ND	ND	ND
ethylbenzene	ND	ND	ND	ND
methylene chloride	ND	ND	ND	ND
methyl chloride	ND	ND	ND	ND
methyl bromide	ND	ND	ND	ND
bromoform	ND	ND	ND	ND
dichlorobromomethane	ND	ND	ND	ND
trichlorofluoromethane	ND	ND	ND	ND
dichlorodifluoromethane	ND	ND	ND	ND
chlorodibromomethane	ND	ND	ND	ND
tetrachloroethylene	ND	ND	ND	ND
toluene	ND	ND	ND	ND
trichloroethylene	ND	ND	ND	ND
vinyl chloride	ND	ND	ND	ND
OTHER: (ug/l)				
xylene	ND	ND	ND	ND
dichlorofluoromethane	ND	ND	ND	ND
acetone	ND	ND	ND	ND
isopropanol	ND	ND	ND	ND
methyl ethyl ketone	ND	ND	ND	ND
butanol	ND	ND	ND	ND
C-7 alkane	ND	ND	ND	ND
methyl isobutyl ketone	ND	ND	ND	ND
hexanol	ND	ND	ND	ND
C-3 benzene	ND	ND	ND	ND
C-9 alkane	ND	ND	ND	ND
trichlorotrifluoroethane	ND	ND	ND	ND
dichlorotrifluoroethane	ND	ND	ND	ND
C-6 alkane	ND	ND	ND	ND
hexanol	ND	ND	ND	ND
C-8 ketone	ND	ND	ND	ND
aldehyde	ND	ND	ND	ND
tetrahydrofuran	ND	ND	ND	ND
dioxane	ND	ND	ND	ND
pentanol	ND	ND	PRESENT	ND

ND = Not Detected

PRIORITY POLLUTANT ANALYTICAL RESULTS
GROUNDWATER MONITORING WELL S/ 1NG

Location: Holden, Mass
Sampling Date July, 1981

VOLATILES (ug/l)	MONITORING WELL REFERENCE NUMBER(S)		
	Dump Well	001	002
acrolein	ND	ND	ND
acrylonitrile	ND	ND	ND
benzene	ND	ND	ND
carbon tetrachloride	ND	ND	ND
chlorobenzene	ND	ND	ND
1,2-dichloroethane	ND	ND	ND
1,1,1-trichloroethane	ND	ND	ND
1,1-dichloroethane	ND	ND	ND
1,1,2-trichloroethane	ND	ND	ND
1,1,2,2-tetrachloroethane	ND	ND	ND
chloroethane	ND	ND	ND
2-chloroethylvinyl ether	ND	ND	ND
chloroform	ND	ND	ND
1,1-dichloroethylene	ND	ND	ND
1,2-trans-dichloroethylene	ND	ND	ND
1,2-dichloropropane	ND	ND	ND
1,3-dichloropropylene	ND	ND	ND
ethylbenzene	ND	ND	ND
methylene chloride	ND	ND	ND
methyl chloride	ND	ND	ND
methyl bromide	ND	ND	ND
bromoform	ND	ND	ND
dichlorobromomethane	ND	ND	ND
trichlorofluoromethane	ND	ND	ND
dichlorodifluoromethane	ND	ND	ND
chlorodibromomethane	ND	ND	ND
tetrachloroethylene	ND	ND	ND
toluene	ND	ND	ND
trichloroethylene	ND	ND	ND
vinyl chloride	ND	ND	ND
OTHER: (ug/l)			
xylene	ND	ND	ND
dichlorofluoromethane	ND	ND	ND
acetone	ND	ND	ND
isopropanol	ND	ND	ND
methyl ethyl ketone	ND	ND	ND
butanol	ND	ND	ND
C-7 alkane	ND	ND	ND
methyl isobutyl ketone	ND	ND	ND
hexanol	ND	ND	ND
C-3 benzene	ND	ND	ND
C-9 alkane	ND	ND	ND
trichlorotrifluoroethane	ND	ND	ND
dichlorotrifluoroethane	ND	ND	ND
C-6 alkane	ND	ND	ND
hexanol	ND	ND	ND
C-8 ketone	ND	ND	ND
aldehyde	ND	ND	ND
tetrahydrofuran	ND	ND	ND

ND = Not Detected

POTENTIAL HAZARDOUS WASTE SITE IDENTIFICATION AND PRELIMINARY ASSESSMENT

[illegible]

NOTE: This form is completed for each potential hazardous waste site to help set priorities for site inspection. The information submitted on this form is based on available records and may be updated on subsequent forms as a result of additional inquiries and on-site inspections.

GENERAL INSTRUCTIONS: Complete Sections I and III through X as completely as possible before Section II (*Preliminary Assessment*). File this form in the Regional Hazardous Waste Log File and submit a copy to: U.S. Environmental Protection Agency; Site Tracking System; Hazardous Waste Enforcement Task Force (EN-335); 401 M St., SW; Washington, DC 20460.

I. SITE IDENTIFICATION

A. SITE NAME Holden Town Dump		B. STREET (or other identifier) Harris Street	
C. CITY Holden MA	D. STATE MASS	E. ZIP CODE 01520	F. COUNTY NAME Worcester
G. OWNER/OPERATOR (if known) 1. NAME Town of Holden		2. TELEPHONE NUMBER	
H. TYPE OF OWNERSHIP <input type="checkbox"/> 1. FEDERAL <input type="checkbox"/> 2. STATE <input type="checkbox"/> 3. COUNTY <input checked="" type="checkbox"/> 4. MUNICIPAL <input type="checkbox"/> 5. PRIVATE <input type="checkbox"/> 6. UNKNOWN			

1. SITE DESCRIPTION

Municipal Dump	
J. HOW IDENTIFIED (i.e., citizen's complaints, OSHA citations, etc.)	K. DATE IDENTIFIED (mo., day, & yr.)
EPA - John Hackler	5/1/80
L. PRINCIPAL STATE CONTACT	
1. NAME	2. TELEPHONE NUMBER
SABIN LOND MADWPC (EAST)	617 726-6373

II. PRELIMINARY ASSESSMENT (complete this section last)

A. APPARENT SERIOUSNESS OF PROBLEM

☒ 1. HIGH ☐ 2. MEDIUM ☐ 3. LOW ☐ 4. NONE ☐ 5. UNKNOWN

RECOMMENDATION

☐ 1. NO ACTION NEEDED (no hazard)

☒ 2. IMMEDIATE SITE INSPECTION NEEDED

a. TENTATIVELY SCHEDULED FOR: _____

b. WILL BE PERFORMED BY: _____

☒ 3. SITE INSPECTION NEEDED

a. TENTATIVELY SCHEDULED FOR: 2 MAY 1980

b. WILL BE PERFORMED BY: DAVID W. TORPOFF

☐ 4. SITE INSPECTION NEEDED (low priority)

C. PREPARER INFORMATION

1. NAME <i>David W. Telford</i>	2. TELEPHONE NUMBER <i>617/223-7265</i>	3. DATE (mo., day, & yr.) <i>5/25/80</i>
------------------------------------	--	---

III. SITE INFORMATION

A. SITE STATUS <input checked="" type="checkbox"/> 1. ACTIVE (Those industrial or municipal sites which are being used for waste treatment, storage, or disposal on a continuing basis, even if infrequently).		<input type="checkbox"/> 2. INACTIVE (Those sites which no longer receive wastes).	<input type="checkbox"/> 3. OTHER (specify): (Those sites that include such incidents like "midnight dumping" where no regular or continuing use of the site for waste disposal has occurred.)
B. IS GENERATOR ON SITE? <input checked="" type="checkbox"/> 1. NO <input type="checkbox"/> 2. YES (specify generator's four-digit SIC Code): _____			
C. AREA OF SITE (in acres) 15	D. IF APPARENT SERIOUSNESS OF SITE IS HIGH, SPECIFY COORDINATES 1. LATITUDE (deg.-min.-sec.) 42° 22' 40.3N 2. LONGITUDE (deg.-min.-sec.) 71° 49' 16.9"W		
E. ARE THERE BUILDINGS ON THE SITE? <input type="checkbox"/> 1. NO <input checked="" type="checkbox"/> 2. YES (specify): <u>BARN FOR PAYLOADER</u>			

WASTE RELATED INFORMATION (contin.)

3. LIST SUBSTANCES OF GREATEST CONCERN WHICH MAY BE ON THE SITE (place in descending order of hazard).

Trichloroethane
 Trichloroethylene
 Benzene
 Toluene
 Cresol Ethyl Benzene

4. ADDITIONAL COMMENTS OR NARRATIVE DESCRIPTION OF SITUATION KNOWN OR REPORTED TO EXIST AT THE SITE.

Actual Discharge site is on
 DPW Property - NOT THE DUMP

VI. HAZARD DESCRIPTION

A. TYPE OF HAZARD	B. POTENTIAL HAZARD (mark 'X')	C. ALLEGED INCIDENT (mark 'X')	D. DATE OF INCIDENT (mo., day, yr.)	E. REMARKS
1. NO HAZARD				
2. HUMAN HEALTH	✓			
3. NON-WORKER INJURY/EXPOSURE	✓			
4. WORKER INJURY				
5. CONTAMINATION OF WATER SUPPLY	✓			
6. CONTAMINATION OF FOOD CHAIN	✓			
7. CONTAMINATION OF GROUND WATER	✓	✓	2 MAY 80	GROUND WATER IS POLLUTED
8. CONTAMINATION OF SURFACE WATER	✓	✓	2 MAY 80	THE QUINAPROST RIVER
9. DAMAGE TO FLORA/FAUNA	✓			
10. FISH KILL	✓			
11. CONTAMINATION OF AIR	✓	✓	2 MAY 80	SMALLS LIKE A SEWER
12. NOTICEABLE ODORS	✓	✓	2 MAY 80	" " " "
13. CONTAMINATION OF SOIL	✓	✓	2 MAY 80	Red deposit
14. PROPERTY DAMAGE				
15. FIRE OR EXPLOSION				
16. SPILLS/LEAKING CONTAINERS/ RUNOFF/STANDING LIQUIDS				
17. SEWER, STORM DRAIN PROBLEMS				
18. EROSION PROBLEMS				
19. INADEQUATE SECURITY				
20. INCOMPATIBLE WASTES	✓			
21. MIDNIGHT DUMPING	✓			
22. OTHER (specify):				

HOLDEN LANDFILL RAMP OUTLINE

10-18-82

EXECUTIVE SUMMARY

- Introduction
- Statement of Problem
- Purpose of Remedial Action Master Plan
- General Approach
- Initial Remedial Measures
- Remedial Investigation
- Source Control Remedial Actions
- Off-site Remedial Actions
- Schedule and Cost of Remedial Planning Activities

1.0 DATA COMPILATION AND EVALUATION

- 1.1 Objective
- 1.2 Behavior of Contaminants in the Environment
- 1.3 Background
 - A. Site Location
 - B. Environmental Setting
 - C. Site History
 - D. Previous Investigations
- 1.4 Data Requirements

2.0 REMEDIAL PLANNING ACTIVITIES

- 2.1 Introduction
 - A. General Description of Remedial Planning Activities
 - B. Development of a Comprehensive List of Remedial Action Alternatives
- 2.2 Community Relations Plan
- 2.3 Initial Remedial Measures
 - A. Site-specific objectives
 - B. Identification and evaluation of initial remedial measures
 - a. Sampling/analysis of private wells on Malden Street in Holden and town wells in West Boylston
 - b. Installation of fence and warning signs at locations of contaminated surface water drainage (Red Brook)
 - C. Implementation of Initial Remedial Measures

Holden Landfill Ramp Outline - continued

2.4 Source Control Remedial Actions

- A. Site-specific Objectives
- B. Identification of Data Requirements
- C. Preliminary evaluation and initial screening of source control remedial actions
 - a. No action
 - b. Interception/treatment of contaminated groundwater
 - c. In-situ encapsulation of contaminant source(s)
 - d. Removal of contaminant source(s) followed by secure disposal
 - e. Combinations of the above actions
- D. Detailed Feasibility Study of Remaining Source Control Remedial Actions and Selection of Appropriate Action(s)
- E. Design/Implementation of Selected Source Control Remedial Action(s)
- F. Long-term On-site Monitoring

2.5 Off-Site Remedial Actions

- A. Specific Objectives
- B. Identification of Data Requirements
- C. Preliminary Evaluation and Initial Screening of Off-site Remedial Actions
 - a. No Action
 - b. Interception/treatment of contaminated groundwater
 - c. Interception/treatment of contaminated surface water drainage
 - d. Removal of contaminated soil followed by secure disposal
 - e. Operational modifications to Wachusett Reservoir system
 - f. Combinations of the above actions
- D. Detailed Feasibility Study of Remaining Off-site Remedial Action(s)
- E. Design/Implementation of Selected Off-site Remedial Actions(s)

ROUTING AND TRANSMITTAL SLIP

Date

4/7/82

TO: (Name, office symbol, room number,
building, Agency/Post)

Initials

Date

1.

Steve Mangione

2.

3.

4.

5.

Action	File	Note and Return
Approval	For Clearance	Per Conversation
As Requested	For Correction	Prepare Reply
Circulate	<input checked="" type="checkbox"/> For Your Information	See Me
Comment	Investigate	Signature
Coordination	Justify	

REMARKS

Holden Land Fill
inorganic

DO NOT use this form as a RECORD of approvals, concurrences, disposals,
clearances, and similar actions

FROM: (Name, org. symbol, Agency/Post)

Room No.—Bldg.

Chuck Larson

Phone No.

3-4630

5041-102

OPTIONAL FORM 41 (Rev. 7-76)
Prescribed by GSA
FPMR (41 CFR) 101-11.206

Holden Landfill Ramp Outline -- continued

3.0 REMEDIAL INVESTIGATION WORK PLAN

- 3.1 Introduction
- 3.2 Safety and Health Plan
- 3.3 Sampling Protocol/Quality Control Plan
- 3.4 Sampling/Analysis of Surface Water
- 3.5 Determine Contaminant Dilution Rates and Water Quality in the Quinapoxet River and Wachusett Reservoir
- 3.6 Perform Risk Analysis of Withdrawals from Wachusett Reservoir
- 3.7 Interpret Data Obtained During Previous Geophysical Studies
- 3.8 Installation/Sampling/analysis of Groundwater Monitoring Wells
- 3.9 Conduct Aquifer Pump Test(s) and Treatability Studies

4.0 SCHEDULE AND COST ESTIMATES OF REMEDIAL PLANNING ACTIVITIES

- 4.1 Community Relations Plan
- 4.2 Initial Remedial Measures
- 4.3 Remedial Investigation
- 4.4 Feasibility Studies - Source Control and Off-site Remedial Actions
- 4.5 Design of Selected Remedial Action(s)
- 4.6 Implementation of Selected Remedial Action(s)
- 4.7 Long-term On-site Monitoring

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF RESEARCH AND DEVELOPMENT
DRINKING WATER RESEARCH DIVISION
LABORATORY REPORT OF DRINKING WATER EXAMINATION
CHEMICAL ANALYSISat Boylston, Mass.
Boston-Wachusett watershedQuinnipiac River - just above I-190 Bridge site
t below all leachate streams ~ 100' below streamNew
S - Special Reg. I

SERIAL NO. OF WATER SAMPLE

54465

DATE OF SAMPLING

DATE
COMPOSITE
STARTED

MO. DAY

ENDING DATE
OF COMPOSITE
OR DATE OF
GRAB SAMPLEMO. DAY YR.
11 03 81

TURBIDITY (1 t.u.)*

58

CALCIUM

27 31

COLOR (15 c.u.)**

35

MAGNESIUM

33 37

TOTAL DISSOLVED
SOLIDS (500)**

70

HARDNESS
as CaCO₃

11 14

CHLORIDE (250)**

18

ALKALINITY
as CaCO₃

17 20

SULFATE (250)**

15

SPECIFIC
CONDUCTANCE98 MICROMOHS
AT 25 C.

NITRATE -N (10.)*

3

pH (6.5-8.5)**

7.1

SODIUM

82

CHROMIUM (TOTAL)
(FURNACE) (.05)*

0.05

LITHIUM

36 39

SILVER (0.05)*

0.03

BARIUM (1.)*

2

COPPER (1.0)**

0.02

ARSENIC
(0.05)*(FURNACE)

0.05

MANGANESE (0.05)**
(SPECT.)

0.06

SELENIUM (0.01)*
(FURNACE)

0.05

LEAD (0.05)* (FURNACE)

0.05

FLUORIDE (1.4 to 2.4)*

1

IRON (0.3)** (SPECT.)

27

SILICON

22 25

CADMIUM (0.010)* (FURNACE)

0.002

ALUMINUM

51 55

ZINC (5)**

0.02

MERCURY (0.002)*

0.0005

REMARKS:

*Primary MCL

**Secondary MCL

All values are milligrams per liter unless otherwise noted.

LAB. NO.

4859

Date Completed

10-3-82
5-10-82

EPA 8 (CIN)
12/81
J. Boylston, Mass.
Boston - Wachuset Res.
on Landfill - main leachate stream at Quinapoxet River
Paw

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE C. RESEARCH AND DEVELOPMENT
DRINKING WATER RESEARCH DIVISION
LABORATORY REPORT OF DRINKING WATER EXAMINATION
CHEMICAL ANALYSIS

Red Brook at confluence
w/ Q.R.

- Special - Reg I SERIAL NO. OF WATER SAMPLE

DATE OF SAMPLING DATE COMPOSITE MO. DAY OF COMPOSITE MO. DAY YR. OR DATE OF GRAB SAMPLE
11 03 81

TURBIDITY (1 t.u.)*

9 12

CALCIUM

27 31

COLOR (15 c.u.)**

13

MAGNESIUM

33 37

TOTAL DISSOLVED SOLIDS (500)**

16 20

HARDNESS as CaCO₃

11 14

CHLORIDE (250)**

21 24

ALKALINITY as CaCO₃

17 20

SULFATE (250)**

<
25 28

SPECIFIC CONDUCTANCE

9 12 (MICROMOHS AT 25 C)

NITRATE -N (10.)*

<
29 31

pH (6.5-8.5)**

14 16

SODIUM

32 35

CHROMIUM (TOTAL) (FURNACE) (0.05) *

<
17 21

LITHIUM

36 39

SILVER (0.05)*

<
23 27

BARIUM (1.)*

<
40 44

COPPER (1.0)**

<
28 32

ARSENIC (0.05)*(FURNACE)

<
51 54

MANGANESE (0.05) ** (SPECT.)

34 38

SELENIUM (0.01)* (FURNACE)

<
56 59

LEAD (0.05)* (FURNACE)

<
40 44

FLUORIDE (1.4 to 2.4)*

56 60

IRON (0.3)** (SPECT.)

2
46 50

SILICON

22 26

CADMIUM (0.010)* (FURNACE)

<
58 62

ALUMINUM

51 55

ZINC (5)**

<
64 68

56 61

MERCURY (0.002)*

<
75 79

62 67

REMARKS:

*Primary MCL

**Secondary MCL

All values are milligrams per liter unless otherwise noted.

LAB. NO. 4860

Date Completed 3-10-82

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF RESEARCH AND DEVELOPMENT
DRINKING WATER RESEARCH DIVISION
LABORATORY REPORT OF DRINKING WATER EXAMINATION
CHEMICAL ANALYSIS

Row

WS-Special-Reg I

SERIAL NO. OF WATER SAMPLE

54462

Red Brook beneath
Power line

DATE OF SAMPLING

DATE
COMPOSITE
STARTED

MO. DAY

ENDING DATE
OF COMPOSITE
OR DATE OF
GRAB SAMPLE

MO. DAY YR.
11 03 81

TURBIDITY (1 t.u.)*

330

CALCIUM

COLOR (15 cu.)**

12

MAGNESIUM

TOTAL DISSOLVED
SOLIDS (500)**

501

HARDNESS
as CaCO₃

CHLORIDE (250)**

100

ALKALINITY
as CaCO₃

SULFATE (250)**

< 15

SPECIFIC
CONDUCTANCE

982

MICROMOHS
AT 25 C

NITRATE -N (10.)*

< 3

pH (6.5-8.5)**

8.1

SODIUM

940

CHROMIUM (TOTAL)
(FURNACE) (.05) *

< .005

LITHIUM

SILVER (0.05)*

< .03

BARIUM (1.)*

< 2

COPPER (1.0)**

< .02

ARSENIC
(0.05)*(FURNACE)

< .005

MANGANESE (0.05) **
(SPECT.)

7.10

SELENIUM (0.01)*
(FURNACE)

< .005

LEAD (0.05)* (FURNACE)

< .005

FLUORIDE (1.4 to 2.4)*

2

IRON (0.3)** (SPECT.)

229

SILICON

CADMIUM (0.010)* (FURNACE)

< .002

ALUMINUM

ZINC (5)**

< .02

MERCURY (0.002)*

< .0005

REMARKS:

*Primary MCL

**Secondary MCL

All values are milligrams per liter unless otherwise noted.

LAB. NO.

4261

Date Completed

3-10-82

U.S. E. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF STANDARDIZATION AND POLLUTION CONTROL
DRINKING WATER RESEARCH DIVISION

Holden, Mass.
Holden Town Dump
other

LABORATORY REPORT OF DRINKING WATER EXAMINATION

Well # HTD W02 - State of Mass. Monitoring Well
no. 75' to water Table

CHEMICAL ANALYSIS

HTD W02

SERIAL NO. OF WATER SAMPLE

54469

DATE OF SAMPLING

DATE
COMPOSITE
STARTED

MO. DAY
[][] [][]

ENDING DATE
OF COMPOSITE
OR DATE OF
GRAB SAMPLE

MO. DAY YR.
11 03 81

TURBIDITY (1 t.u.)*

340

CALCIUM

[][][][]

COLOR (15 c.u.)**

25

MAGNESIUM

[][][] [][][]

TOTAL DISSOLVED
SOLIDS (500)**

575

HARDNESS
as CaCO₃

[][][][]

CHLORIDE (250)**

100

ALKALINITY
as CaCO₃

[][][][]

SULFATE (250)**

< 15

SPECIFIC
CONDUCTANCE

1160 MICROMOHS
AT 25 C

NITRATE -N (10.)*

< 3

pH (6.5-8.5)**

8.3

SODIUM

112

CHROMIUM (TOTAL)
(FURNACE) (0.05)*

0.08

LITHIUM

[][] [][][]

SILVER (0.05)*

< 0.03

BARIUM (1.)*

32

COPPER (1.0)**

0.09

ARSENIC
(0.05)*(FURNACE)

< 0.05

MANGANESE (0.05)**
(SPECT.)

1.84

SELENIUM (0.01)*
(FURNACE)

< 0.05

LEAD (0.05)* (FURNACE)

0.12

FLUORIDE (1.4 to 2.4)*

2

IRON (0.3)** (SPECT.)

12.5

SILICON

[][][] [][]

CADMIUM (0.010)* (FURNACE)

0.03

ALUMINUM

[][][] [][]

ZINC (5)**

2.30

MERCURY (0.002)*

< 0.005

REMARKS:

*Primary MCL

**Secondary MCL

All values are milligrams per liter unless otherwise noted.

LAB. NO.

4862

Date Completed

10-3-82
3-10-82

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF RESEARCH AND DEVELOPMENT
DRINKING WATER RESEARCH DIVISION

LABORATORY REPORT OF DRINKING WATER EXAMINATION

CHEMICAL ANALYSIS

Holden, Mass.

"Town Dump"

other

Holden Town Dump - Well #HTD W05 - State of Mass. Monitoring Well
8' 2 1/2" to water tableRaw
Special - Reg I

SERIAL NO. OF WATER SAMPLE

54470

DATE OF SAMPLING

DATE
COMPOSITE
STARTED

MO. DAY

ENDING DATE
OF COMPOSITE
OR DATE OF
GRAB SAMPLE

MO. DAY YR.

11 03 81

TURBIDITY (1 t.u.)*

4 10 12

COLOR (15 c.u.)*

30 13

TOTAL DISSOLVED
SOLIDS (500)**

701 16 20

CHLORIDE (250)**

150 21 24

SULFATE (250)**

< 15 25 28

NITRATE -N (10.)*

< 3 29 31

SODIUM

180 32 35

LITHIUM

36 39

BARIUM (1.)*

< 2 40 44

ARSENIC
(0.05)*(FURNACE)

< 005 51 54

SELENIUM (0.01)*
(FURNACE)

< 005 56 59

FLUORIDE (1.4 to 2.4)*

2 66 68

SILICON

22 25

ALUMINUM

51 55

56 61

62 67

CALCIUM

27 31

MAGNESIUM

33 37

HARDNESS
as CaCO₃

11 14

ALKALINITY
as CaCO₃

17 20

SPECIFIC
CONDUCTANCE1373 (MICROMOHS
AT 25 C.) 9 12

pH (6.5-8.5)**

8.2 14 16

CHROMIUM (TOTAL)
(FURNACE) (.05)*

012 17 21

SILVER (0.05)*

< 03 23 27

COPPER (1.0)**

06 28 32

MANGANESE (0.05)**
(SPECT.)

3 00 34 38

LEAD (0.05)* (FURNACE)

010 40 44

IRON (0.3)** (SPECT.)

12.2 46 50

CADMIUM (0.010)* (FURNACE)

002 58 62

ZINC (5)**

4.42 64 68

MERCURY (0.002)*

< 0005 75 79

REMARKS:

*Primary MCL

**Secondary MCL

All values are milligrams per liter unless otherwise noted.

LAB. NO.

4863

Date Completed

10-3-81
3-10-82

PUNCH IN COLS.

IDENTIFICATION OF WATER SAMPLE

1 3

1. LOCATION OF WATER SUPPLY METROPOLITAN DISTRICT COMMISSION
CITY, COUNTY, STATE BOSTON (CLINTON, MA)

FOR OFFICE USE ONLY

DO NOT
WRITE BELOW
THIS LINE

2. WATER SUPPLY NAME INDC

3. DATE OF SAMPLING

BEGINNING DATE OF COMPOSITE	MO.	DAY	ENDING DATE OF COMPOSITE OR DATE OF GRAB SAMPLE	MO.	DAY	YR.
				11	03	81
20		23	24			29

4. SAMPLE FROM ☐ TREATMENT PLANT ☐ WELL ☒ RESERVOIR ☐ DISTRIBUTION SYSTEM ☐ OTHER

5. SAMPLING POINT
LOCATION AND/OR
DESCRIPTION WACHUSETTS RESERVOIR - ENTRANCE
TO AQUEDUCT

6. TYPE OF WATER SAMPLED ☐ FINISHED ☐ PARTIALLY TREATED ☒ RAW *BEFORE TURBINE* ☐ OTHER

7. SOURCE OF WATER ☒ SURFACE ☐ GROUND ☐ COMBINED ☐ OTHER

8. SAMPLING METHOD ☐ COMPOSITE ☒ GRAB ☐ OTHER

9. ANALYSIS REQUIRED ☒ ORGANIC ☐ TRACE ELEMENTS ☐ WET ☐ RADIO-CHEMICAL ☐ OTHER

10. WATER SUPPLY CATEGORY ☒ 8 COMMUNITY WATER SUPPLY ☒ 4 ICWS ☐ 2 FEDERAL INSTALLATION ☒ 1 SPECIAL STUDY ☐ 0 OTHER

11. APPEARANCE OF SAMPLE _____

12. ADDITIONAL REMARKS _____

13. COLLECTED BY C. LARSON & D. CHIN ☒ STAFF ☐ OTHER

DO NOT WRITE BELOW THIS LINE

LAB. SAMPLE NO. _____ DATE RECEIVED _____
LABORATORY REMARKS _____

OVER FOR INSTRUCTIONS

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF WATER PROGRAMS
WATER SUPPLY DIVISION

SERIAL NO.
54454

DUPLICATE IN COPIES.

IDENTIFICATION OF WATER SAMPLE

1 6

1. LOCATION OF WATER SUPPLY

W. BOYLSTON
CITY, COUNTY, STATE

MA.

FOR OFFICE
USE ONLY

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

7

19

2. WATER SUPPLY NAME

MDC - BOSTON

DO NOT
WRITE BELOW
THIS LINE

3. DATE OF SAMPLING

BEGINNING
DATE OF
COMPOSITE

MO.

DAY

20				23	

ENDING DATE
OF COMPOSITE
OR DATE OF
GRAB SAMPLE

MO.

DAY

YR.

11	03	81			
24				29	

4. SAMPLE FROM

☐

TREATMENT
PLANT

☐

WELL

☐

RESERVOIR

☐

DISTRIBUTION
SYSTEM

☒

OTHER

☐

30

5. SAMPLING POINT

LOCATION AND/OR
DESCRIPTION

QUINAPOXET RIVER AT HORSESHOE DAM

☐

31

32

6. TYPE OF
WATER
SAMPLED

☐

FINISHED

☐

PARTIALLY
TREATED

☒

RAW

☐

OTHER

☐

34

7. SOURCE
OF WATER

☒

SURFACE

☐

GROUND

☐

COMBINED

☐

OTHER

☐

35

8. SAMPLING
METHOD

☐

COMPOSITE

☒

GRAB

☐

OTHER

☐

36

9. ANALYSIS
REQUIRED

☒

VOA
ORGANIC

☐

TRACE
ELEMENTS

☐

WET

☐

RADIO-
CHEMICAL

☐

OTHER

☐

37

10. WATER
SUPPLY
CATEGORY

☒

COMMUNITY
WATER
SUPPLY

☐

IGWS

☐

FEDERAL
INSTALLATION

☒

SPECIAL
STUDY

☐

OTHER

☐

38

40

11. APPEARANCE OF SAMPLE CLEAR

12. ADDITIONAL REMARKS

13. COLLECTED BY

☒

STAFF

☐

OTHER

☐

80

DO NOT WRITE BELOW THIS LINE

LAB. SAMPLE NO.

DATE RECEIVED

LABORATORY REMARKS

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF WATER PROGRAMS OPERATIONS
WATER SUPPLY DIVISION

SERIAL NO.
54465

PUNCH IN COLS.

IDENTIFICATION OF WATER SAMPLE

1 6

1. LOCATION OF WATER SUPPLY WEST BOYLSTON, MA
CITY, COUNTY, STATE

FOR OFFICE USE ONLY

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

7 19

DO NOT
WRITE BELOW
THIS LINE

2. WATER SUPPLY NAME MDC - BOSTON - WACHUSETT WATERSHED

3. DATE OF SAMPLING

BEGINNING DATE OF COMPOSITE	MO.	DAY	ENDING DATE OF COMPOSITE OR DATE OF GRAB SAMPLE	MO.	DAY	YR.
	20	23		11	03	81
				24		29

4. SAMPLE FROM ☐ TREATMENT PLANT ☐ WELL ☐ RESERVOIR ☐ DISTRIBUTION SYSTEM ☒ OTHER

8 4 2 1 0 30

5. SAMPLING POINT LOCATION AND/OR DESCRIPTION QUINAROXET RIVER JUST ABOVE I-190 BRIDGE SITE

31 32

6. TYPE OF WATER SAMPLED ☐ FINISHED ☐ PARTIALLY TREATED ☒ RAW AND JUST BELOW ALL LEACHATE STREAMS (ABOUT 100' DOWNSTREAM) ☐ OTHER

8 4 2 0 34

7. SOURCE OF WATER ☒ SURFACE ☐ GROUND ☐ COMBINED ☐ OTHER

8 4 2 0 35

8. SAMPLING METHOD ☐ COMPOSITE ☒ GRAB ☐ OTHER

8 4 0 36

9. ANALYSIS REQUIRED ☒ ORGANIC ☐ TRACE ELEMENTS ☐ WET ☐ RADIO-CHEMICAL ☐ OTHER

8 4 2 1 0 37

10. WATER SUPPLY CATEGORY ☒ COMMUNITY WATER SUPPLY ☐ ICWS ☐ FEDERAL INSTALLATION ☒ SPECIAL STUDY ☐ OTHER

8 4 2 1 0 38 40

11. APPEARANCE OF SAMPLE

12. ADDITIONAL REMARKS

13. COLLECTED BY LARSON & CHIN ☒ STAFF ☐ OTHER

1 80

DO NOT WRITE BELOW THIS LINE

LAB. SAMPLE NO. DATE RECEIVED
LABORATORY REMARKS

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF WATER POLLUTION CONTROL OPERATIONS
WATER SUPPLY DIVISION

SERIAL NO.
54466

PUNCH IN COLS.

IDENTIFICATION OF WATER SAMPLE

1. LOCATION OF WATER SUPPLY

W. BOYLSTON - MA.
CITY, COUNTY, STATE

FOR OFFICE
USE ONLY

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

7

MASSACHUSETTS RESERVOIR

2. WATER SUPPLY NAME

MDC - BOSTON WATERSHED

DO NOT
WRITE BELOW
THIS LINE

3. DATE OF SAMPLING

BEGINNING DATE OF COMPOSITE MO. DAY 20 23
ENDING DATE OF COMPOSITE OR DATE OF GRAB SAMPLE MO. DAY YR. 11 03 81
24 29

4. SAMPLE FROM

☐ TREATMENT PLANT ☐ WELL ☐ RESERVOIR ☐ DISTRIBUTION SYSTEM ☒ OTHER

5. SAMPLING POINT

LOCATION AND/OR
DESCRIPTION

HOLDEN LANDFILL NEW LEACHATE BREAKOUT

6. TYPE OF
WATER
SAMPLED

☐ FINISHED ☐ PARTIALLY TREATED ☒ RAW ☐ OTHER
DUMP LEACHATE

7. SOURCE
OF WATER

☐ SURFACE ☒ GROUND ☐ COMBINED ☐ OTHER
COMING OUT OF GROUND BELOW LAND FILL

8. SAMPLING
METHOD

☐ COMPOSITE ☒ GRAB ☐ OTHER

9. ANALYSIS
REQUIRED

☒ ORGANIC ☐ TRACE ELEMENTS ☐ WET ☐ RADIO-CHEMICAL ☐ OTHER

10. WATER
SUPPLY
CATEGORY

☒ COMMUNITY WATER SUPPLY ☐ ICWS ☐ FEDERAL INSTALLATION ☒ SPECIAL STUDY ☐ OTHER

11. APPEARANCE OF SAMPLE

12. ADDITIONAL REMARKS

STRONG ODOR - IRON PRECIPITATE ON GROUND

13. COLLECTED BY

LARSON & CHIN

☒ STAFF ☐ OTHER

DO NOT WRITE BELOW THIS LINE

LAB. SAMPLE NO.

DATE RECEIVED

LABORATORY REMARKS

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF WATER PROGRAMS OPERATIONS
WATER SUPPLY DIVISION

58407

PUNCH IN COLS.

IDENTIFICATION OF WATER SAMPLE

1 6

1. LOCATION OF WATER SUPPLY

W. BOYLSTON, WORCESTER, MA.
CITY, COUNTY, STATE

FOR OFFICE
USE ONLY

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

7

19

2. WATER SUPPLY NAME

MPC-BOSTON - WACHUSETT RESERVOIR

DO NOT
WRITE BELOW
THIS LINE

3. DATE OF SAMPLING

BEGINNING
DATE OF
COMPOSITE

MO.

DAY

20		23	

ENDING DATE
OF COMPOSITE
OR DATE OF
GRAB SAMPLE

MO.

DAY

YR.

1	1	0	3	8	1
24				29	

4. SAMPLE FROM

☐

TREATMENT
PLANT

☐

WELL

☐

RESERVOIR

☐

DISTRIBUTION
SYSTEM

☒

OTHER

8

4

2

1

0

☐

30

5. SAMPLING POINT
LOCATION AND/OR
DESCRIPTION

HOLDEN LANDFILL
MAIN LEACHATE STREAM AT QUINAPOKET RIVER

☐

31

32

6. TYPE OF
WATER
SAMPLED

☐

FINISHED

☐

PARTIALLY
TREATED

☒

RAW

☐

OTHER

8

4

2

0

☐

34

7. SOURCE
OF WATER

☐

SURFACE

☒

GROUND

☐

COMBINED

☐

OTHER

8

4

2

0

☐

35

8. SAMPLING
METHOD

☐

COMPOSITE

☒

GRAB

☐

OTHER

8

4

0

☐

36

9. ANALYSIS
REQUIRED

☒

ORGANIC

☐

TRACE
ELEMENTS

☐

WET

☐

RADIO-
CHEMICAL

☐

OTHER

8

4

2

1

0

☐

37

10. WATER
SUPPLY
CATEGORY

☒

COMMUNITY
WATER
SUPPLY

☐

ICWS

☐

FEDERAL
INSTALLATION

☒

SPECIAL
STUDY

☐

OTHER

8

4

2

1

0

☐

38

40

11. APPEARANCE OF SAMPLE

12. ADDITIONAL REMARKS

STRONG ODOR - IRON PRECIPITATE ON ROCKS

13. COLLECTED BY

LARSON & CHIN

☒

STAFF

☐

OTHER

☐

80

DO NOT WRITE BELOW THIS LINE

LAB. SAMPLE NO.

DATE RECEIVED

LABORATORY REMARKS

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF WATER PROGRAMS OPERATIONS
WATER SUPPLY DIVISION

SERIAL NO.
54468

PUNCH IN COLS.

IDENTIFICATION OF WATER SAMPLE

1 6

1. LOCATION OF WATER SUPPLY

W. BOYLSTON MA
CITY, COUNTY, STATE

FOR OFFICE
USE ONLY

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

7

RESERVOIR

19

2. WATER SUPPLY NAME

MDC - BOSTON WACHUSETT WATERSHED

DO NOT
WRITE BELOW
THIS LINE

3. DATE OF SAMPLING

BEGINNING
DATE OF
COMPOSITE

MO.

DAY

--	--	--	--	--	--

20

23

ENDING DATE
OF COMPOSITE
OR DATE OF
GRAB SAMPLE

MO.

DAY

YR.

1	1	0	3	8	1
---	---	---	---	---	---

24

29

4. SAMPLE FROM

☐

TREATMENT
PLANT

☐

WELL

☐

RESERVOIR

☐

DISTRIBUTION
SYSTEM

☒

OTHER

☐

30

5. SAMPLING POINT
LOCATION AND/OR
DESCRIPTION

HOLDEN LANDFILL LEACHATE NEAR BREAKOUT

OLD UNDER POWER LINE

--	--	--

31

33

6. TYPE OF
WATER
SAMPLED

☐

FINISHED

☐

PARTIALLY
TREATED

☒

RAW

☐

OTHER

☐

34

7. SOURCE
OF WATER

☐

SURFACE

☒

GROUND

☐

COMBINED

☐

OTHER

☐

35

8. SAMPLING
METHOD

☐

COMPOSITE

☒

GRAB

LEACHATE

☐

OTHER

☐

36

9. ANALYSIS
REQUIRED

☒

ORGANIC

☐

TRACE
ELEMENTS

☐

WET

☐

RADIO-
CHEMICAL

☐

OTHER

☐

37

10. WATER
SUPPLY
CATEGORY

☒

COMMUNITY
WATER
SUPPLY

☐

ICWS

☐

FEDERAL
INSTALLATION

☒

SPECIAL
STUDY

☐

OTHER

--	--	--

38

40

11. APPEARANCE OF SAMPLE

YELLOW - TURBID

12. ADDITIONAL REMARKS

ODOR - IRON PRECIPITATE

13. COLLECTED BY

LARSON & CHIN

☒

STAFF

☐

OTHER

☐

80

DO NOT WRITE BELOW THIS LINE

LAB. SAMPLE NO.

DATE RECEIVED

LABORATORY REMARKS

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF WATER RESOURCES OPERATIONS
WATER SUPPLY DIVISION

SERIAL NO.
54469

PUNCH IN COLS.

IDENTIFICATION OF WATER SAMPLE

1 6

1. LOCATION OF WATER SUPPLY

HOLDEN WORCESTER MA
CITY, COUNTY, STATE

FOR OFFICE
USE ONLY

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

7

19

2. ~~WATER SUPPLY~~ NAME

HOLDEN TOWN DUMP

DO NOT
WRITE BELOW
THIS LINE

3. DATE OF SAMPLING

BEGINNING
DATE OF
COMPOSITE

MO.

DAY

20

23

ENDING DATE
OF COMPOSITE
OR DATE OF
GRAB SAMPLE

MO.

DAY

YR.

11

03

81

29

4. SAMPLE FROM

☐

TREATMENT
PLANT

☐

WELL

☐

RESERVOIR

☐

DISTRIBUTION
SYSTEM

☒

OTHER

☐

30

5. SAMPLING POINT
LOCATION AND/OR
DESCRIPTION

40.75' TO WATER TABLE

WELL # HTDW02 - STATE OF MASS MONITORING

☐

31

6. TYPE OF
WATER
SAMPLED

☐

FINISHED

☐

PARTIALLY
TREATED

☒

RAW

☐

OTHER

☐

34

7. SOURCE
OF WATER

☐

SURFACE

☒

GROUND

☐

COMBINED

☐

OTHER

☐

35

8. SAMPLING
METHOD

☐

COMPOSITE

☒

GRAB

☐

OTHER

☐

36

9. ANALYSIS
REQUIRED

☒

VQA
ORGANIC

☐

TRACE
ELEMENTS

☐

WET

☐

RADIO-
CHEMICAL

☐

OTHER

☐

37

10. WATER
SUPPLY
CATEGORY

☐

COMMUNITY
WATER
SUPPLY

☐

ICWS

☐

FEDERAL
INSTALLATION

☒

SPECIAL
STUDY

☐

OTHER

☐

38

11. APPEARANCE OF SAMPLE

12. ADDITIONAL REMARKS

13. COLLECTED BY LARSON, GUN

☒

STAFF

☐

OTHER

☐

80

DO NOT WRITE BELOW THIS LINE

LAB. SAMPLE NO.

DATE RECEIVED

LABORATORY REMARKS

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF WATER PROGRAMS OPERATIONS
WATER SUPPLY DIVISION

SERIAL NO.
54470

PUNCH IN COLS.

IDENTIFICATION OF WATER SAMPLE

1 6

1. LOCATION OF WATER SUPPLY

HOLDEN, WORCESTER, MASS.

CITY, COUNTY, STATE

FOR OFFICE
USE ONLY

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

7

19

DO NOT
WRITE BELOW
THIS LINE

2. WATER SUPPLY NAME

HOLDEN TOWN DUMP

3. DATE OF SAMPLING

BEGINNING
DATE OF
COMPOSITE

MO. DAY
20 23

ENDING DATE
OF COMPOSITE
OR DATE OF
GRAB SAMPLE

MO. DAY YR.
11 03 81
24 29
2pm

4. SAMPLE FROM

☐ TREATMENT
8 PLANT

☐ WELL
4

☐ RESERVOIR
2

☐ DISTRIBUTION
1 SYSTEM

☒ OTHER
0

☐
30

5. SAMPLING POINT
LOCATION AND/OR
DESCRIPTION

HOLDEN TOWN DUMP WELL #HWDW05

STATE OF MASS.
MONITORING WELL

☐
31

33

6. TYPE OF
WATER
SAMPLED

☐ FINISHED
8

☐ PARTIALLY
4 TREATED

☒ RAW
2

8 1/2" TO WATER
TABLE

☐ OTHER
0

☐
34

7. SOURCE
OF WATER

☐ SURFACE
8

☒ GROUND
4

☐ COMBINED
2

☐ OTHER
0

☐
35

8. SAMPLING
METHOD

☐ COMPOSITE
8

☒ GRAB
4

☐ OTHER
0

☐
36

9. ANALYSIS
REQUIRED

☒ ORGANIC
8

☐ TRACE
4 ELEMENTS

☐ WET
2

☐ RADIO-
1 CHEMICAL

☐ OTHER
0

☐
37

10. WATER
SUPPLY
CATEGORY

☐ COMMUNITY
8 WATER
SUPPLY

☐ ICWS
4

☐ FEDERAL
2 INSTALLATION

☒ SPECIAL
1 STUDY

☐ OTHER
0

☐
38

40

11. APPEARANCE OF SAMPLE

12. ADDITIONAL REMARKS

VERY STRONG ODOR "GARLIC"

13. COLLECTED BY

LARSON & CHIN

☒ STAFF

☐ OTHER

☐
1

60

DO NOT WRITE BELOW THIS LINE

LAB. SAMPLE NO.

DATE RECEIVED

LABORATORY REMARKS

